

Kerala State Drugs & Pharmaceuticals Ltd						
Name of Work: KSDP- LABOUR WORK FOR PROVIDING MS PIPE RACKS AT NON BETALACTAM & BETALACTAM PROJECT.						
QUOTATION NO. KSDP/PRJ/NONBETA/PIPELINESTR/2018-19/02						
SCHEDULE						
Date of Submission : 12.11.2018, 11.00 hrs				Date of Opening : 12.11.2018, 12.00 hrs		
Sl.No.	Description	Qty	Unit	Rate		Amount
				In figures	In words	
1	Labour charges for the Fabrication,Painting(1 coat prime + 2 coat Epoxy) and Erection of utility line pipe racks (MS) from betalactam Aircompressor room to nonbetalactam utility room ,betalactam plant and water Treatment Plant for a distance of 100 M approximately by using company supplied MS channel,angles etc complete as per the following specification and as directed by the department officers cocern.	1500	KG			
a	Distance between each pipe racks shall be of 3 meters					
b	Minimum height clearance of 4.5 meter shall required at the road crossing area .					
c	Pipe supports fabrication using angles at the PEB area.					
d	Bridges shall be provided using MS structure whenever road crossing is coming.					
2	All the civil works required for the completion of the above said work also in the contractor's scope.Earth works where ever required, like Trenching,Side brick wall,Foundations for pillar supports as directed by the officer concerned.	1	Lumps			
<b>Total</b>						
Total in words						

**NOTE:** The quantity mentioned above is as per the initial drawing and estimate and likely change as per the site conditions.Hence the payment will be done as per the actual work done .

Contractor's Name:

Address:

HOD  
Projects

Phone No: