



Kerala State Drugs & Pharmaceuticals Ltd.
a government of Kerala enterprise

Factory & Office :
Kalavoor, Alappuzha - 688 522, India
Phone: 0477-2258184, 2258828
Telefax : 0477-2258162
E-mail: ksdpltd@gmail.com
Website : www.ksdp.co.in

KSDP/PRJ / STR / 2022-23 /01

20/04/2022

ദർഘാസ് വിജ്ഞാപനം

കെ എസ് ഡി പി യി - ലെ നോൺബീറ്റാലാക്ടം പ്ലാന്റിന്റെ EPOXY RECTIFICATION WORK ചെയ്യുന്നതിനായി പ്രവൃത്തിപരിചയമുള്ള വ്യക്തികൾ / കോൺട്രാക്ടർ എന്നിവർക്ക് കമ്പനിയിൽ നിന്നും സീൽഡ് ദർഘാസ് ക്ഷണിക്കുന്നു. കോട്ട് ചെയ്യാൻ ആഗ്രഹിക്കുന്ന വ്യക്തികൾക്ക് / കോൺട്രാക്ടർക്ക് കമ്പനിയിൽ നേരിട്ട് വന്ന് പ്രോജക്ട് ഓഫീസുമായി ബന്ധപ്പെട്ട ശേഷം സെറ്റ് കാണാവുന്നതാണ്. സീൽഡ് ദർഘാസ് സമർപ്പിക്കേണ്ട അഭികാമ്യമായരൂപം പ്രോജക്ട് ഓഫീസിൽ നിന്നും, കമ്പനി വെബ്സൈറ്റ് ആയ www.ksdp.co.in നിന്നും ലഭിക്കുന്നതാണ്.


- Sealed tender Submission Fee: 1,200/- (Including GST)
- Earnest Money Deposit (EMD) : Rs. 11,761/-

സീൽഡ് ദർഘാസ് കവറിനു മുകളിൽ “EPOXY RECTIFICATION WORK IN GROUND, SECOND AND SERVICE FLOOR OF NON-BETALACTAM PLANT” എന്ന് എഴുതി “മാനേജിംഗ് ഡയറക്ടർ”, കെ എസ് ഡി പി, കലവൂർ ആലപ്പുഴ എന്ന വിലാസത്തിൽ സമർപ്പിക്കേണ്ടതാണ്.

സീൽഡ് ദർഘാസ് സ്വീകരിക്കുന്ന അവസാന തീയതി : 26/04/2022; 11.00 AM.

സീൽഡ് ദർഘാസ് തുറക്കുന്ന തീയതി : 26/04/2022; 11.30 AM.

കൂടുതൽ വിവരങ്ങൾക്ക് കെ.എസ്.ഡി.പി പ്രോജക്ട് ഓഫീസുമായി ബന്ധപ്പെടുക.

എന്ന്,

ഡെപ്യൂട്ടി മാനേജർ
(പ്രോജക്ട്)



kerala state drugs and pharmaceuticals ltd.

a government of kerala enterprise

factory & office phone : 0477-2258184
kalavoor - 688 522 0477-2258828
atappuzha, india

Email: ksdpitd@gmail.com fax : 0477 - 2258162
Website: www.ksdp.co.in

SEALED TENDER DETAILS

Name of Work: EPOXY RECTIFICATION WORK IN GROUND, SECOND AND SERVICE FLOOR OF NON-BETALACTAM PLANT

Sealed Tender publishing date : 20/04/2022

Closing date : 26/04/2022; 11.00 AM

Opening date : 26/04/2022; 11.30 AM

TERMS AND CONDITIONS

1. Scope of the Work :

Epoxy Rectification Work in Ground, Second and Service Floor Of Non Beta Lactum Plant as per the specification mentioned in BOQ.

2. Period of Completion :

All the work should be completed within 15 days from the date of issue of work order / Handing over of Site.

3. Compensation for delay :

Time is the essence of the contract. If the contractor fails to complete the work and clear the site on or before the dates fixed for the completion, he shall without prejudice be liable to pay liquidation damage (LD), i.e. 1 (one) percent of the contract value for every week that the whole or the part of work remains incomplete. For the purpose of this condition, the contract value shall be total value of quantities of items in the contract at contract rates plus algebraic sum of the subsequent work ordered. However, the total amount of LD to be paid under this condition shall not exceed 10 (ten) percent of the contract value.

4. Terms of Payment :

- I. Running account bills will be made according to the progress of the works. In addition to performance security, retention for the work will be deducted from the running/final bill of contractors @ 2.5% of the gross amount of each running bill and will be released along with the final bill.
- II. The 5% of Performance Security, Deposited along with the agreement will be released 30 days after successful completion of the works on submission of a bank guarantee for the equal amount which will be released after 18 months from the date of completion if there is no rectification / deformity of works are found.

Tax Deduction:- All statutory deduction other than GST like Income tax, E.S.I., P.F., KWWF, or any other government imposed liability shall be borne by the contractor (as applicable at the time of execution of job / payment of bills) and shall be deducted from each bill submitted by the contractor. Any other aspects not mentioned in this will be as per the store purchase manual /PWD manual.


5. General Terms.

- i. You are directed to attend this office within 3 days from the date of issue of work order with a Kerala stamp paper worth Rs. 200/-.
- ii. Before executing the agreement on stamp paper worth Rs 200/-, you should deposit a performance security of 5% of accepted PAC for the due fulfillment of the contract. Performance security can be remitted in any mode as per Store Purchase Manual.
- iii. Further time of 3 days shall be allowed to execute agreement by imposing a fine at 1% of the quoted PAC subject to a minimum of Rs 600/- and maximum of Rs 15,000/-
- iv. Your Tender will be rejected if agreement is not executed within 6 days from the date of issue of Selection Notice and work will be awarded to the next lowest Tenderer.
- v. EMD will be returned after execution of agreement.
- vi. Any failure in this direction will be liable to result in the forfeiture of the Earnest money already deposited and cancellation of the proposed contract and the contractor shall be liable to pay the Company the entire loss that may be caused to the company by the tenderer or re-arrangement of the work or otherwise consequent of the contractor's failure to execute the agreement or executing the work provided for, as contemplated in 'Letter of submission of Tender'.
- vii. It must be understood that on no account the rate once fixed will be increased.

6. General Conditions:

- i) You should work as per the Rules & Regulations applicable to Employees of the company.
- ii) You should be responsible for the welfare and safety of the Men employed by you inside the company.
- iii) Statutory deductions if any will apply to the Contract Value
- iv) In case of dispute, jurisdiction will be Alleppey, Kerala

- v) All safety measures should be taken during Erection & Commissioning.
- vi) Water and electricity will be supplied by KSDP free of cost at one point.
- vii) Special care is to be taken for cleanliness of the site & after the end of day's work the site should be cleaned immediately.
- viii) All tools and machines, scaffolding and labours required for the work is coming under the scope of contractor.
- ix) Before starting the works you must produce the documents regarding welfare of employers such as ESI,EPF and insurance.
- x) Your employees should wear all safety items/equipments such as helmet, goggles, safety belts, boots etc. Company will have no liability to employees entrusted by you with respect to safety measures.
- xi) Any items found to be having been executed with poor workmanship or materials of inferior quality then the contractor shall have to rectify / reconstruct the work as specified by owner/ consultant. No extra charge will be admissible in such case. If contractors fails to do so, the owner / consultant reserved the right to rectify reconstruct the through some other agency at the expenses of contractor.
- xii) EMD should be enclosed as DD in favour of Managing Director, Kerala State Drugs and Pharmaceuticals LTD, Alappuzha.


DEPUTY MANAGER PROJECTS
KERALA STATE DRUGS & PHARMACEUTICALS LTD
ALAPPUZHA

KERALA STATE DRUGS AND PHARMACEUTICALS LTD., KALAVOOR, ALAPPUZHA

Name of Work : EPOXY RECTIFICATION WORK IN GROUND, SECOND AND SERVICE FLOOR OF NON-BETALACTAM PLANT

SCHEDULE

Item no	Description	Quantity	Unit	Rate Inc .GST	Amount
1	Chipping, scrapping and cleaning the existing epoxy floor area. Scrapped materials should be removed from the site .Complete as directed by the officers concerned.	250.000	M ²		
2	Applying base primer for epoxy work at a thickness of 200 micron with materials of approved brand, Providing, laying and levelling to get level floor surface , jointless epoxy screeding work of required thickness(minimum 2 mm thick)with materials of approved manufacture.Complete as directed by the officers concerned	250.000	M ²		
3	Providing laying and carry out epoxy priming coat and to apply as per manufactures specification and finally applying, providing ,laying and carry out epoxy top coat of 2mm thick with 3 component system,certified ecofriendly self levelling material,self smooth gloosy as per manufacture specification including cost and conveyance of all materials,labour charges,hire charges of all tools and plants etc..Complete as directed by the officers concerned.	250.000	M ²		
4	Providing laying and carryout coving to floor to wall/panel ,corner,mixing base reactors and fibre silica (50mm to 80mm) vertical height and applying 2coat of epoxy paint of required thickness and to apply as per manufacturing specification and directions of Engineer-in -charge	130.000	M		
5	Apply of epoxy coat of minimum 300 micron thickness in existing epoxy floor area. (Necessary preparation and work required for applying epoxy also to be considered)	50.000	M ²		
	Grand total				
	ROUNDED TO				



Deputy Manager (PROJECTS)

CONTRACTOR