



Kerala State Drugs & Pharmaceuticals Ltd.
a government of Kerala enterprise

Factory & Office :
Kalavoor, Alappuzha - 688 522, India
Phone: 0477-2258184, 2258828
Telefax : 0477-2258162
E-mail: ksdpltd@gmail.com
Website : www.ksdp.co.in

KSDP/PRJ/QTN/2024-25/17

26/10/2024

ദർഘാസ് വിജ്ഞാപനം

കെ.എസ്.ഡി.പി-ലെ ഹൈ മാസ്റ്റ് ലൈറ്റിന്റെ ഇൻസ്റ്റാളേഷൻ വർക്കുകൾ നടന്നുകൊണ്ടിരിക്കുകയാണ്. ഹൈ മാസ്റ്റ് ലൈറ്റിലേക്കുള്ള ഇലക്ട്രിക്കൽ സപ്ലൈ നോൺ ബീറ്റർ ലാക്ട്രം പ്ലാന്റിലെ ഇലക്ട്രിക്കൽ റൂമിൽ നിന്നും എത്തിക്കേണ്ടതുണ്ട്. ഇതുമായി ബന്ധപ്പെട്ട് Cabling for High-mast light എന്ന വർക്കിന് പ്രവൃത്തിപരിചയമുള്ള സി ഗ്രേഡ് ഇലക്ട്രിക്കൽ കോൺട്രാക്ടർമാരിൽ നിന്നും സീൽഡ് ക്യാട്ടേഷൻ ക്ഷണിക്കുന്നു. ക്യാട്ട് ചെയ്യാൻ ആഗ്രഹിക്കുന്ന വ്യക്തികൾക്ക് / കോൺട്രാക്ടർക്ക് കമ്പനിയിൽ നേരിട്ട് വന്ന് പ്രൊജക്റ്റ് ഓഫീസുമായി ബന്ധപ്പെട്ട ശേഷം സൈറ്റ് കാണാവുന്നതാണ്. സീൽഡ് ക്യാട്ടേഷൻ സമർപ്പിക്കേണ്ട മാതൃക പ്രൊജക്റ്റ് ഓഫീസിൽ നിന്നും ലഭിക്കുന്നതാണ്.

സീൽഡ് ക്യാട്ടേഷൻ കവറിനു മുകളിൽ "Cabling for High-mast light" എന്ന് എഴുതി "മാനേജിംഗ് ഡയറക്ടർ", കെ.എസ്.ഡി.പി, എന്ന വിലാസത്തിൽ സമർപ്പിക്കേണ്ടതാണ്.

സീൽഡ് ക്യാട്ടേഷൻ സ്വീകരിക്കുന്ന അവസാന തീയതി : **05/11/2024, 5.00 pm.**

സീൽഡ് ക്യാട്ടേഷൻ തുറക്കുന്ന തീയതി : **06/11/2024, 11.00 am.**

പേയ്മെന്റ് വ്യവസ്ഥകൾ

ജോലി പൂർണ്ണമായ പൂർത്തീകരിച്ചതിനുശേഷം മാത്രമേ പേയ്മെന്റ് നൽകുകയുള്ളൂ. കൂടുതൽ വിവരങ്ങൾക്ക് കെ.എസ്.ഡി.പി പ്രൊജക്റ്റ് ഓഫീസുമായി ബന്ധപ്പെടുക.

പൂർത്തീകരിക്കേണ്ട സമയം

വർക്ക് ഓർഡർ നൽകി 7 ദിവസത്തിനുള്ളിൽ വർക്ക് പൂർത്തീകരിക്കേണ്ടതാണ്.

എന്ന്,

ഡെപ്യൂട്ടി മാനേജർ പ്രോജക്ട്സ്



QUOTATION

26/10/2024

KSDP is Inviting sealed quotations for the work "Cabling for Highmast light"

1. SCOPE OF WORK

Cabling for high-mast light. A detailed work schedule is given in Annexure 1.

2. PERIOD OF COMPLETION

All the work should be completed within 7 days of receiving the work order or handing over the site.

3. TERMS AND CONDITIONS

1. The work should be carried out under a person holding a valid Electrical Contractor Class C License and experience in 3 works of similar kind.
2. All the materials supplied should be as per the list of approved make by KSDP Ltd. A detailed list of approved make is given in Annexure 2.
3. You should work as per the rules and regulations applicable to company employees.
4. You should be responsible for the welfare and safety of the men employed by you inside the company.
5. Statutory deductions if any will apply to the contract value.
6. In case of dispute, the Jurisdiction will be Alleppy, Kerala.
7. All safety measures should be taken during supply and installation.
8. Water and electricity will be supplied by KSDP free of cost at one point.
9. Special care is to be taken for the cleanliness of the site and after the end of day work the site should be cleaned immediately.
10. All tools and machines scaffolding and labourers required for the work come under the scope of the contractor.
11. Your employees should wear all safety items/equipment such as helmets, goggles, safety belts, boots, etc. The company will have no liability to employees entrusted by you with respect to safety measures.
12. Any items found to have been executed with poor workmanship or materials of inferior quality then the contractor shall have to rectify /reconstruct the work as specified by the owner/consultant. No extra charge will be admissible in such cases. If contractors fail to do so, the owner/consultant reserves the right to

rectify or reconstruct it through some other agency at the expense of the contractor.

4. TERMS OF PAYMENT

- a. 100% payment will be released after the completion of the work and certificate of measurement.
- b. Tax Deduction: All statutory deductions other than GST like income tax, ESI, P.F, KWWF, or any other government-imposed liability shall be borne by the contractor (as applicable at the time of execution of job/payment of bills) and shall be deducted from each bill submitted by the contractor. Any other aspects not mentioned in this will be as per the store purchase manual/PWD manual.

IMPORTANT DAYS

Last date of receipt of sealed quotation : **05/11/2024, 5.00 pm.**
Sealed quotation opening date : **06/11/2024, 11.00 am.**

Please send your sealed quotation as per the schedule to The Managing Director, Kerala State Drugs and Pharmaceuticals Ltd, Kalavoor, Alappuzha on or before **05/11/2024, 5.00 pm.**

For any queries, Please feel free to contact the following number.


Mr. Lijesh Joy
Dy. Manager(Project)
Mob: 9496516035



Dy. Manager (Project)

Annexure 1

SCHEDULE

Name of Work: Cabling for High-mast light.

Sl.No	Item description	Unit	Quantity	Rate(Excl GST)	Amount
1	Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35 x 75 cm, refilling the trench etc. as required but excluding sand cushioning and protective covering (in ordinary soil).4 core 16 sq mm Supply and Laying Cable 4cX16 Sqmm Al	Metre	90		
2	Supply & laying of one No. PVC insulated and PVC sheathed armoured aluminium power cable of 1.1 KV grade of the following sizes in the existing masonry open duct as required.4 core 16 sq mm Supply and Laying 4cX16 Sqmm Al cable in open duct	Metre	10		
3	Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV				

	grade of the following sizes in the existing RCC/ HUME / STONE WARE/ GI/ DWC pipe as required.4 core 16 sq mm Supply and Laying 4c X 16 Sqmm Al Cable in GI pipe	Metre	5		
4	Supply and laying of the following sizes of B class GI pipe laid 0.6 m below ground level including excavating trench of suitable size and refilling etc, as required.50 mm dia. G.I. pipe (medium class) Supply and Laying GI pipe	Metre	5		
5	Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required.4 core 16 sq mm with factory made clamp Supply and Clamping 4c X 16 Sqmm Al Cable	Metre	5		
6	Supplying and making end termination with brass compression				

	gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 16 sq. mm (28mm) Cable termination 4C x 16 Sqmm Al	Set	2		
7	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required. Cable root markers	Nos	5		
Grand Total					

GST will be paid extra as actual

Annexure 2

Electrical – List of Approved make		
Sl.No	Item	Manufacturer's Name
1	LT Power and Control Cable	Gloster, Finolex, Polycab, Havells
2	Cable Glands	Comet, Cosmos, Braco, Hex
3	LT Cable Termination	Jainsons, Comet, Dowells, Hex




Dy. Manager (Project)

