



Kerala State Drugs & Pharmaceuticals Ltd.
a government of Kerala enterprise

Factory & Office :
Kalavoor, Alappuzha - 688 522, India
Phone: 0477-2258184, 2258828
Telefax : 0477-2258162
E-mail: ksdpltd@gmail.com
Website : www.ksdp.co.in

KSDP/PRJ/QTN/2025-26/og

19/09/2025

SEALED QUOTATION NOTICE

LVP/SVP ROOF LEAKAGE RECTIFICATION

Inviting sealed quotation for LVP/SVP roof leakage rectification at KSDP, Alappuzha

1. SCOPE OF WORK

LVP/SVP roof leakage rectification at KSDP, Alappuzha. as per the accompanying BOQ (Annexure 1).

2. TERMS OF PAYMENT

100% payment will be released after satisfactory completion of work.

3. PERIOD OF COMPLETION

15 days from the date of issue of work order.

4. SPECIFICATION

Attached as annexure 1.

5. GENERAL CONDITIONS

- i. You should work as per the Rules & Regulations applicable to employees of the company.
- ii. You should be responsible for the welfare and safety of the men employed by you inside the company.

- iii. In case of dispute, jurisdiction will be Alleppey, Kerala.
- iv. All safety measures should be taken during work.
- v. All tools and machines, scaffolding and labourers required for the work is coming under the scope of contractor.
- vi. Your employees should wear all safety items/equipments such as helmet, goggles, safety belts, boots etc. Company will have no liability to employees entrusted by you with respect to safety measures.
- vii. GST will be paid extra as per actual.

6. IMPORTANT DATES :

Last Date of receipt of quotation : **25-09-2025 at 3:30 pm.**

Sealed quotation opening date : **25-09-2025 at 4:00 pm.**

Please send your sealed quotation to Managing Director, Kerala State Drugs And Pharmaceuticals Ltd, Kalavoor, Alappuzha on or before 25-09-2025 at 3:30 pm.

Sd/-

Deputy Manager (Projects)



KERALA STATE DRUGS AND PHARMACEUTICALS LTD KALAVOOR, ALAPPUZHA					
LVP/SVP ROOF LEAKAGE RECTIFICATION					
BOQ (Annexure 1)					
SL.NO	DESCRIPTION	QTY	UNIT	RATE	TOTAL AMOUNT in RS. (Excl.GST)
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	47	sqm		
2	12mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	47	sqm		
3	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge	100	sqm		
	Grand Total (Excl.GST)				
*GST Extra as per actual or TDS will be deducted.					

CONTRACTOR




DEPUTY MANAGER (PROJECT)