



**Kerala State Drugs & Pharmaceuticals Ltd.**  
a government of Kerala enterprise

Factory & Office :  
Kalavoor, Alappuzha - 688 522, India  
Phone: 0477-2258184, 2258828  
Telefax : 0477-2258162  
E-mail: ksdpltd@gmail.com  
Website : www.ksdp.co.in

KSDP/PRJ/QTN/2025-26/ 15

28/01/2026

### **SEALED QUOTATION NOTICE**

#### **Tile Work In Store Toilet And Masonry Work In Water Plant**

Inviting sealed quotation "Tile work in store toilet and masonry work in water plant" at KSDP, Alappuzha

#### **1. SCOPE OF WORK**

Tile work in store toilet and masonry work in water plant at KSDP, Alappuzha. as per the accompanying BOQ (Annexure 1).

#### **2 TERMS OF PAYMENT**

100% payment will be released after satisfactory completion of work.

#### **3 PERIOD OF COMPLETION**

7 days from the date of issue of work order.

#### **4 SPECIFICATION**

Attached as annexure 1.

#### **5. GENERAL CONDITIONS**

- i. You should work as per the Rules & Regulations applicable to employees of the company.
- ii. You should be responsible for the welfare and safety of the men employed by you inside the company.

- iii. In case of dispute, jurisdiction will be Alleppey, Kerala.
- iv. All safety measures should be taken during work.
- v. All tools and machines, scaffolding and labourers required for the work is coming under the scope of contractor.
- vi. Your employees should wear all safety items/equipments such as helmet, goggles, safety belts, boots etc. Company will have no liability to employees entrusted by you with respect to safety measures.
- vii. GST will be paid extra as per actual.

**6. IMPORTANT DATES :**

Last Date of receipt of quotation : 05-02-2026 at 3:30 pm.

Sealed quotation opening date : 05-02-2026 at 4:00 pm.

**Please send your sealed quotation to Managing Director, Kerala State Drugs And Pharmaceuticals Ltd, Kalavoor, Alappuzha on or before 05-02-2026 at 3:30 pm.**



Deputy Manager (Projects)

**KERALA STATE DRUGS AND PHARAMCEUTICALS LTD KALAVOOR, ALAPPUZHA**

**Tile Work In Store Toilet And Masonry Work In Water Plant**

**BOQ (Annexure 1)**

SL.NO	DESCRIPTION	QTY	UNIT	RATE	TOTAL AMOUNT in RS. (Excl.GST)
1	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed vitrified floor tiles polished finish of sizeSize of Tile 600 x 600 mm	6.10	sqm		
2	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete	18.75	sqm		

3	Labour for plumbing works	3	nos		
4	Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in : CM 1:6 ( 1 cement : 6 coarse sand) etc complete	0.35	cum		
5	12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	24.25	sqm		
6	Preparing the roof surface and applying waterproof material and supply of materials,labours ,scaffolding etc. Make: Dr Fix Clear, Asian paints smart care, Acrylic Polymer	17.95	sqm		
	<b>Grand Total (Excl.GST)</b>				

\*GST Extra as per actual or TDS will be deducted.

CONTRACTOR



DEPUTY MANAGER (PROJECT)